

CHITALDRUG DIVISION.

The 13th August 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 10th September 1898, for constructing a new tank near Meerasabihalli village, Challakere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1902.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank Meerasabihalli village, Challakere taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

CONSTRUCTING A NEW TANK, MEERASABIHALLI VILLAGE, CHALLAKERE TALUK,

(CHITALDRUG DISTRICT.)

Items of Work.	Per.	Quantity.	Remarks.
Bund—			
Earthwork (including tamping, &c.)	C. yds.	283,742	
Do from cody cutting	"	7,977	
Clearing silt	"	2,799	
Digging seat of bund	"	2,503	
Baling water	Lump sum Rs.		
Turfing	S. yds.	30,446	
New stone work (including jelly backing)	C. yds.	14,980	
Grade stones	No.	33	
Top width stones	"	33	
B. M. stones	"	2	
Gauge stones	"	2	
Tank No. stone	"	1	
Date stone	"	1	
Weirs—			
Excavation gravelling soil	C. yds.	10,065	
Do hard soil	"	4,693	
Blasting rock	"	7,359	
Earthwork (draining back)	"	4,000	
Burnt brick in chunam	C. ft.	8,307	
Burnt stone slabs	S. ft.	3,322	
Burnt stone in chunam	C. ft.	4,281	
Pointing	Lump sum Rs.		
Plastering	Do		
Rough stone apron	C. yds.	1,088	
Sluices—			
Burnt brick in chunam	C. ft.	31,280	
Stone in chunam	"	826	
Burnt brick in chunam (arch work)	"	2,850	
Burnt stone slabs (6" inches)	S. ft.	1,658	
Do (9" inches)	"	452	
Cut stone work	C. ft.	540	
Pointing	Sqr.	13.20	
Plastering	Sqr.	123.74	
Concrete (3" thick)	"	1.90	
Teakdoors (complete)	No.	2	
Do windows with iron bars	"	6	
Teakwood work	C. ft.	72	
Steel girders	No.	6	
Lifting gear	"	2	
Do with ply	"	8	
Bridge	Lump sum Rs.		

Items of work.	Per.	Quantity.	Remarks.
Irrigation Channels (right to left)—			
Earthwork (excavation)	C. yds.	45,368	
Mile and	No.	16	
Half furlong stone.	"	218	
Grade stone	"	232	
Irrigation Sluices—			
Excavation	C. yds.	185	
Stone in chunam	C. ft.	2,849	
Burnt stone slab	S. ft.	333	
Revetment	C. yd.	37	
Iron pipe	Per foot	529	
Relieving Weirs—			
Earthwork (excavation)	C. yds.	784	
Brick in chunam	C. ft.	43,120	
Burnt stone slabs	S. ft.	3,920	
Plastering with chunam	Sqrs.	2744	
Dry stone	C. yds.	1,176	
Syphons—			
Earthwork	C. yds.	2,572	
Stone in chunam	C. ft.	10,648	
Brick in chunam	"	8,506	
Do arch work	"	2,046	
Concrete	"	160	
Burnt stone slabs	S. ft.	1,182	
Plastering with chunam	Sqrs.	5028	
Rough stone	C. yds.	106	
Cart Bridges—			
Burnt stone slabs	S. ft.	2,100	
Burnt stone in chunam	C. ft.	880	
Pointing with chunam	Sqrs.	2180	
Gravel	C. yds.	2680	
Excavation	"	150	
Cut stone work	C. ft.	1,800	
Guard stones	No.	80	

K. PRAHLADA RAO, *Offg. Exec. Engineer.*

FRENCH ROCKS DIVISION.

The 10th August 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 10th September 1898, for constructing an aqueduct at the 7½ mile of Chickdevarayasagar Channel for the diversion of Mosalehalla drainage, Seringapatam taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 10 A. M. to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The Tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing an aqueduct at the 7½ mile of Chickdevarayasagar Channel" in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.